



ITEM	DESCRIPTION
①	6"x 8"x 16" SLUMPSTONE CONCRETE BLOCK, LAPAZ COLOR
②	6"x 2"x 16" SLUMPSTONE CONCRETE CAP, LAPAZ COLOR
③	POURED CONCRETE FOOTING (SEE NOTE BELOW)

**NOTES:**

1. ALL CELLS SHALL BE SOLID GROUTED
2. CONCRETE IN FOOTING TO BE 3,000 P.S.I. AT 28 DAYS
3. GROUT - 1 PART CEMENT, 3 PARTS SAND, 2 PARTS PEA GRAVEL
4. MORTAR - 1 PART CEMENT, 1/2 PART LIME PUTTY, 4-1/2 PARTS SAND
5. PLASTIC AND MASONRY CEMENT IS NOT ALLOWED PER U.B.C.
6. NO REBAR SHALL BE INSTALLED WITHIN 3" OF ANY SUBSURFACE CONCRETE EDGE
7. FOOTINGS SHALL BEAR ON COMPETENT UNDISTURBED NATURAL SOIL OR STRUCTURAL BACKFILL. REMOVE ALL LOOSE MATERIAL BEFORE CONCRETE PLACEMENT.

REVISION DATE: 3/31/2011

SAN BERNARDINO MUNICIPAL WATER DEPARTMENT

DRAWING NUMBER

**CONCRETE MASONRY FENCE DETAIL  
(NOT TO BE USED FOR RETAINING EARTH)**

SBMWD

W6.23

APPROVED

*[Signature]*  
MATTHEW H. LITCHFIELD, P.E. RCE 58079

DATE

10/11/11

D.D.M. MAR. 11

REVISION DATE

SCALE: NONE